

BILL TO ADDRESS:

**JUBILANT LIFE SCIENCES LIMITED**

PLOT 1A, SECTOR-16A

NOIDA, UTTAR PRADESH - 201301

COMPANY :929 PROJECT - NOIDA - CORPORATE

State : 09 Uttar Pradesh

GSTIN : 09AABCV0200H1ZU

**PURCHASE ORDER**

PO No. : 160009 Order Dt: 21-08-2017 Project : LS1276	Delivery Date : 20-09-2017 Buyer : Sanjay Jaiswal Reference A : LS1276 GQCS-4803	Transaction Type : Domestic Inter State Nature of Transaction : From Registered Vendor Reference B :
Supplier/Vendor: GJ0333	Ship From : GJ0333 S01	Ship To :
JAGRAJ CONSTRUCTION CO  SHOP NO.1,UMA SHANKAR C H SOC. GR FLR,SVP ROAD,OPP PLASMA BLOOD BANK,DOMBIVLI-EAST  Pincode : 421201 State : 27 Maharashtra GSTIN : 27AARPI6697Q1ZE Email :	Jagraj Construction Co.  Shop No. 1, Ground floor, Uma Shankar Co-op Hsg. Soc.LTD SVP ROAD, DOMBIVLI  Pincode : 421201 State : 27 Maharashtra GSTIN : 27AARPI6697Q1ZE Email :	JUBILANT LIFE SCIENCES LIMITED PLOT 1A, SECTOR-16A NOIDA, UTTAR PRADESH - 201301  Pincode : State : 09 Uttar Pradesh GSTIN : 09AABCV0200H1ZU

Dear Sir,

Please supply the following goods as per the terms and conditions stipulated below and overleaf.

Item Code	HSN	Quantity	UOM	Unit Price	Basic Amount	Disc. Amt	Other Charges1	Other Charges2	Taxable Value	Integrated Tax Amount	Total Amount
9300061E		1.00	--	411342.50	411342.50	0.00	0.00	0.00	411342.50	74041.65	485384.15
Civil Work BOQ / Rsate schedule / Job description as per following BOQ :											
SL.NO.	ITEM	QTY	UNIT	Rate	Amount						
TURNSTILE CANOPY & FENCING											
1	Earth work in excavation in foundation trenches to any depth or drains including dressing of sides and ramming of bottom including by watering, stacking the serviceable earth as directed and getting out the excavated earth including disposal of surplus soil as directed.	34	Cum	175	5950						
2	Filling in foundation and plinth with available soil at site free from organic and inorganic content in layers of 20 cm thickness including watering, ramming and consolidating etc. complete as directed by Engineer.	23.5	Cum	190	4465						
3	"Plain cement concrete (1:4:8) in foundations, plinth, etc for all depth below plinth level including centering, shuttering, machine mixing, laying consolidating, curing etc. as specified including dewatering subsoil or rainwater if any, all materials and labour complete. (The batching of concrete shall be done by volume/weight as per consultant's instruction).	6.8	Cum	5275	35870						
4	"Providing & laying M 25 grade of reinforced cement concrete work in col pedestal,plinth beam, col footing, raft, cable / pipe trench, grade slab and mass concrete excluding the cost of centering, shuttering & reinforcement, as per dwgs and directed by Consultant.	2.5	Cum	7200	18000						



BILL TO ADDRESS:

**JUBILANT LIFE SCIENCES LIMITED**

PLOT 1A, SECTOR-16A

NOIDA, UTTAR PRADESH - 201301

COMPANY :929 PROJECT - NOIDA - CORPORATE

State : 09 Uttar Pradesh

GSTIN : 09AABCV0200H1ZU

Dear Sir,

Please supply the following goods as per the terms and conditions stipulated below and overleaf.

Item Code Description	HSN	Quantity	UOM	Unit Price	Basic Amount	Disc. Amt	Other Charges1 /	Other Charges2 /	Taxable Value	Integrated Tax Amount	Total Amount
a) The fabrication work shall start only after approval of the fabrication drawings. Any change required in the fabrication drawing shall be carried out at no extra cost.											
b) Fabrication shall be in a perfect Architectural workmanship manner and as provided in Section V & VI of IS 800 & IS 7215.											
c) Welding shall be carried out by qualified welders.											
d) Electrodes for welding, the procedure, selection, test and inspection shall confirm to provisions in IS 816, IS 818, IS 822 & IS 833.											
e) Erection / hoisting shall commence only after approval of fabricated parts by the project Manager.											
11 Structural steel works with MS rolled sections angles, channels etc. conforming to IS 2062.											
i)	ISMC 150 & ISMC 75	226	KG	45	10170						
12 Structural steel works with MS plate sections.											
iii)	MS plate 05mm th & 12mm th.	72	KG	45	3240						
13 Providing and fixing aluminium composite panel of 4mm th. 35 microns DFT and PVDF coated aluminium cladding of ALUCCO-BOND, ALUCCOMAT or REYNOBOND of approved shade and colour for external wall either segment of straight in plan and around corners and wherever else specified, fixed to masonry or concrete as required with extruded aluminium 'U' section, angles, cleats, SS screws, rivets and brackets including necessary drilling, silicon weather sealant, gasket and other necessary accessories etc. all complete as per manufacturers specification and directions of engr. in charge. The fixing shall be done on to MS frames duly corrosion resistant painted, at anchorage locations, in walls, Glazing jambs, cills and heads etc by drilling holes with an electric drill, inserting fasteners, stainless steel counter sunk screws etc. 21											
sq.mt	2200	46200									
14 Providing, fabricating and fixing in position, SS 304 fencing with hollow tube sections, base plates, in modular formation. The fencing shall be in brush finish. 532 kg 250 133000											
MISCELLANEOUS WORKS											
1 Dismantling all types of flooring as directed, including breaking of underfloor upto 100 depth (overall) and disposal of unserviceable material within 50 metres lead. 51 Sq.M. 150 7650											
2 Earth work in excavation for laying new flooring and its underlayers, to any depth including dressing of sides and ramming of bottom including by watering, stacking the serviceable earth as directed and getting out the excavated earth including disposal of surplus soil as directed. 2.5 Cum											
250	625										
3 Filling in foundation, embankment and plinth with selected cohesive,											

BILL TO ADDRESS:

**JUBILANT LIFE SCIENCES LIMITED**

PLOT 1A, SECTOR-16A

NOIDA, UTTAR PRADESH - 201301

COMPANY :929 PROJECT - NOIDA - CORPORATE

State : 09 Uttar Pradesh

GSTIN : 09AABCV0200H1ZU

Dear Sir,

Please supply the following goods as per the terms and conditions stipulated below and overleaf.

Item Code Description	HSN	Quantity	UOM	Unit Price	Basic Amount	Disc. Amt	Other Charges1 /	Other Charges2 /	Taxable Value	Integrated Tax Amount	Total Amount
non swelling earth brought from outside free from organic and inorganic content in layers of 20 cm thickness including watering, ramming and consolidating etc. complete as directed by Engineer. (Yellow Soil)		0.7	Cum	500	350						
4 Providing and laying rouble soling filling with sand as filler including watering, ramming consolidating and dressing complete, in specified thickness, as directed.		0.7	Cum	2150	1505						
5 "Plain cement concrete (1:4:8) in foundations, plinth, etc for all depth below plinth level including centering, shuttering, machine mixing, laying consolidating, curing etc. as specified including dewatering subsoil or rainwater if any, all materials and labour complete. (The batching of concrete shall be done by volume/weight as per consultant's instruction).		0.3	Cum	5275	1582.5						
6 "Providing & laying M 25 grade of reinforced cement concrete work in col pedestal,plinth beam, col footing, raft, cable / pipe trench, grade slab and mass concrete excluding the cost of centering, shuttering & reinforcement, as per dwgs and directed by Consultant.		0.75	Cum	7200	5400						
7 Centering and shuttering including strutting , propping etc and removal of form for col pedestal, plinth beam, col footing, grade slab,cable / pipe trench etc and mass concrete.		2	Sqm	450	900						
8 "Laying and fixing in position HYSD bar reinforcement (FE-500grade) as per IS : 1786, for RCC in situ and precast work including cost of straightening, cutting, bending and binding with 16 gauge MS annealed binding wire, cement mortar spacer blocks etc. complete as per drawing, specifications, and as directed by the Engineer up to all heights & depth. All chairs, laps, spacers are payable, but as per actual measurement.		102	kg	20	2040						
9 Providing and laying 32mm thick stone flooring over 20mm (average) thick base with joints 5 mm thick including pointing with cement mortar 1:2 (1 cement: 2 stone dust) with an admixture of pigment to match the shade of stone with base 1:5(1cement:5coarse sand) :											
a) With 32 mm th. SAND BLASTED BLACK GRANITE.		5.7	Sq.m		3250						
18525											
Total					411342.5						

Note :

&gt; GST - @18%

&gt; Completion schedule : Within 2 months from the date of intimation from Jubilant.

&gt; L.D. Clause : Not applicable.

&gt; Payment terms : 95% against running bill within 15 days

&amp; 05% retention shall be paid on completion of work after

6 months with reconciliation of free issue material by Jubilant.

BILL TO ADDRESS:

**JUBILANT LIFE SCIENCES LIMITED**

PLOT 1A, SECTOR-16A

NOIDA, UTTAR PRADESH - 201301

COMPANY :929 PROJECT - NOIDA - CORPORATE

State : 09 Uttar Pradesh

GSTIN : 09AABCV0200H1ZU

Dear Sir,

Please supply the following goods as per the terms and conditions stipulated below and overleaf.

Item Code Description	HSN	Quantity	UOM	Unit Price	Basic Amount	Disc. Amt	Other Charges1 /	Other Charges2 /	Taxable Value	Integrated Tax Amount	Total Amount
GQCS.4803/RFQ.5059/QCS.7198 dt. 09.05.17											

Grand Total	: (INR) ( FOUR LAKHS EIGHTY FIVE THOUSAND THREE HUNDRED EIGHTY FOUR AND FIFT	<b>485384.15</b>
-------------	--	------------------

INTEGRATED TAX : (INR) 74041.65 (SEVENTY FOUR THOUSAND FORTY ONE AND SIXTY FIVE PAISE ONLY )

Reverse Charge Payable : NO

TDS Applicable(1%)(Yes/No):

Delivery Terms:C10 DELIVERED AT PLACE

Payment Terms:U10 As Mentioned in PO Text

INDENTOR

1.State our Order and Item Number on all invoices

2.All columns of E-way bill to be filled.

3.Time is the essence of this Purchase Order

4.In case of Material rejection,Jubilant will send back/book the consignment on "To Pay" basis at supplier risk and the copy of lorry receipt of the Transporter will be consider as a proof of material.

Place :NOIDA

Date : 21-08-2017

FOR JUBILANT LIFE SCIENCES LIMITED

Prepared By

Checked By

AUTHORIZED SIGNATORY

THIS IS A COMPUTER GENERATED PURCHASE ORDER AND HENCE DOES NOT REQUIRE ANY SIGNATURE.